



- Project:** IMAS (Institute for Marine and Antarctic Studies) Pump Station – Mechelec
- The pump station supplies seawater to the IMAS research facility controlled by the pumps and switchboards located in the concrete panel building.
- Location:** Tarooma, Tasmania
- Principal:** University of Tasmania
- Project Scope:** Mechanical and Electrical works included installation of sea water intakes to each of three pump sets. Installation of pump sets, vacuum bleeding system, compressed air purging system, sound proofed air extraction system. All electrical sub boards, control systems including emergency genset installation. Safety stairs, walkways and platforms.
- Contract Value:** \$2.8M
- Project Year:** 2019/20
- Project Duration:** 3 months
- Contract Type:** Contact and Variation Sum
- Unique Compliance:** Work within local community on the foreshore, managing a busy pedestrian walkway between pump station and foreshore.